

UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM

TENDER SCHEDULE FOR RENOVATION OF THE SHUTTLE COURT, PROVIDING SITTING BENCH, LEVELLING YARD, COVERING SLABS ABOVE THE SIDE DRAIN IN THE RESEARCH'S MEN'S HOSTEL AT KARIAVATTOM CAMPUS. (RETENDER)						
Sl. No	Qty	Description in work	Unit	Rate	Rate in words	Amount in Rupees
1	110	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	m ²	30.90	Rupees Thirty and Ninety paise only	3399.00
2	0.46	2.1.1 Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to bevelled and neatly dressed: All Kinds of soil	m ²	73.10	Rupees Seventy Three and Ten paise only	33.63
3	5.5	50.4.1.1 Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) up to floor five level excluding the cost of centering, shuttering, finishing for leveling coarse of floor and roof etc	m ³	7522.02	Rupees Seven Thousand Five Hundred and Twenty Two and paise Two only	41371.11
4	5	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	m ³	6176.71	Rupees Six thousand One hundred and seventy Six and Seventy One paise only	30883.55
5	0.5	6.4.2 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:6 (1 cement : 6 coarse sand)	m ³	7700.43	Rupees Seven Thousand Seven Hundred and Forty Three paise only	3850.22

6	77	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	kg
7	1.1	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	m³
8	5.2	5.9.1 Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	m²
9	110	13.7.1 12 mm cement plaster finished with a floating coat of neat cement of mix: 1:3 (1 cement : 3 fine sand)	m²
10	12.86	13.1.1 12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	m²
11	45	10.1 Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg
12	105	od191210/2019_2020 Drawing court lines up to 5 cm wide using approved paint in white/yellow colour as approved as per departmental direction	RM

78.07	Rupees Seventy Eight and seven paise only	6011.39
7561.25	Rupees Seven thousand Five hundred sixty One and Twenty Five paise only	8317.375
267.52	Rupees Two hundred Sixty Seven paise Fifty Two only	1391.10
312.83	Rupees Three hundred Twelve paise Eighty Three only	34411.30
238.55	Rupees Two hundred Thirty Eight paise Fifty Five only	3067.753
80.62	Rupees Eighty paise Sixty Two only	3627.90
80.74	Rupees Eighty paise Seventy Four only	8477.70

