

UNIVERSITY OF KERALA

SUBDIVISION II KARIAVATTOM

TENDER SCHEDULE FOR THE TILING IN GROUND FLOOR CORRIDOR, TOILET AREA AND CAR PORCH IN THE DEPARTMENT OF ARABIC AT KARIYAVATTOM CAMPUS.

Sl. No	Item Description	Qty	Unit	Rate / Unit	Rate in Words	Amount
1)	11.49.2 Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS : 15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	108	sqm	1895.07	One Thousand Eight hundred and Ninty Five and Seven Paisa only	204667.56
2)	od235582/2021_2022 Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness including pointing the joints with white cement and matching pigment etc., complete	26	sqm	1167.66	One Thousand One hundred and Sixty Seven Rupees and Sixty Six Paisa only	30359.16
Carporch Tiling						
1)	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.5	cum	7,990.86	Seven Thousand Nine hundred andNinty Rupees and Eighty Six Paisa only	3995.43

2)	15.2.1 Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	1.4	cum	2045.12	Two Thousand and Forty five Rupees and Twelve Paisa only	2863.17
3)	11.20.4 Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand). Ordinary cement without any pigment	50	sqm	1027.09	One Thousand and Twenty Seven Rupees and Nine Paisa only	51354.50
	TOTAL:					293239.82
	GRAND TOTAL after round off:					293240.00

Rs.2,93,240/-(Rupees Two Lakh Ninty Three Thousand Two Hundred and Forty only)

I / Weagree to undertake the above mentioned work:-

- 1) At the estimate rate.
- 2) At% below the estimate rate.
- 3) At% above the estimate rate.

Rate should be quoted both in figures and words

CONTRACTOR

ASSISTANT EXECUTIVE ENGINEER II