

**University of Kerala**  
**Engineering Unit, Kariavattom**

**TENDER SCHEDULE FOR THE SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF AIR CONDITIONING UNITS FOR THE UPGRADATION OF DOIC, ALAPPUZHA (RETENDER)**

Sl.No.	Quantity	Specification	Unit	Rate	Amount
1	4 Nos.	Supply, conveyance, installation testing and commissioning of 2 TR 5 star split Air Conditioner unit inverter type with low power consumption high wall mounted suitable for operating on 230 V, 50 Hz, single phase AC supply and fitted with rotary compressor operating on R410 A CFC refrigerent with copper condensing coil and evoporating units capable for cooling dehumidifying air circulating microprocessor control with cordless remote etc. including refrigerent, electrive cable copper pipe and thermal insulation up to 3.5 M as required with two year on site waranty, 5 year compressor warranty and one year free service. (Voltas/Blue star/Daikan/Carrier/Panasonic) 100% copper.	E		
2	4 Nos.	Supply of 5 KVA Voltage stabilizer for split type AC unit with voltage range of 210-240V with 3 years warranty and 3 months replacement waranty (V guard)	E		
3	4 sets	Supply and providing Condenser Stand	E		
	5 M	Supply of extra length copper pipe with thermal insulation (if necessary)	M		

**PAC Rs.**

I/We agreed at quoted rate.

**CONTRACTOR**

sd/-  
**UNIVERSITY ENGINEER**