

<b>Sl. No.</b>	<b>Description</b>	<b>Qty</b>
<b>(I) ACTIVE COMPONENTS</b>		
1	24 Port10/100/1000Mbps unmanageable rack mount Giga-switch-Brand : D-Link/TP-Link/HP/	1 No.
<b>(II) PASSIVE COMPONENTS</b>		
2	Cat6 4UTP cable	305 Mtrs
3	Cat6 Information outlet-Brand : Molex	17 Nos
4	Cat6 Face plate singlex- Brand:Molex	15 Nos
5	3 X 3 surface mount box	15 Nos
6	Cat 6 patch cord, 3 mtr-Brand: Molex	10 Nos
7	Cat6 patch cord, 1 mtr-Brand: Molex	16 Nos
8	RJ 45 connector	2 Nos
9	Cat 6 patch panel 24 port-Loaded-Brand: Molex	1 No.
10	20 mm ISI PVC conduit with all accessories – Ivory	50 Mtrs
11	25 mm ISI PVC conduit with all accessories – Ivory	70 Mtrs
12	6U rack with Accessories [Fan 1 Nos, PDU, Cable Manager 1 Nos]	1 No.
<b>(III) LABOUR CHARGES</b>		
13	UTPCable laying charges	305Mtrs
14	Conduit laying charges	120Mtrs
15	Fixing, Termination, Testing & Labelling of information outlet	17 Nos
16	Fixing, Labelling and port termination of patch panel	1 No.
17	Fixing of wall mount rack with anger bolts, Labelling of patch code & Dressing	1 No.
<b>(IV) ELECTRICAL</b>		
18	Two numbers of 2.5 sq.mm and one number of 1.5 sq mm PVC insulated copper wire	20 Mtrs
19	One number of 6A socket controlled by 1 switch with surface mount box – Modular	1 No.

\* Billing is done as per actual requirements.