

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: UNIVERSITY ENGINEER

Work Name : QUOTATION SCHEDULE FOR RELAYING THE ROOFING WITH RAILWAY PATTERN TILES IN THE ORI & MSS LIBRARY AT KARIAVATTOM CAMPUS, THIRUVANANTHAPURAM

Contract No: UE/Qtn.No.2/2019-20

Bidder Name :						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	RATE IN WORDS	NUMBER #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P		TOTAL AMOUNT With Taxes
1	2	4	5	13	51	54
1	To prevent the leakage of rain water in ORI and Manuscripts Library building by removing the existing Railway pattern roofing tiles and relaying t					
1.01	od9191/2018_2019 : Dismantling and removing the railway pattern roofing tiles and stacking materials at convenient location as per departmental direction	800.00	sqm			
1.02	od21949/2018_2019 : Fixing on roof pressed clay tile (Railway pattern tile) of 20 mm nominal thickness and of approved size and as per approved pattern(old and new tiles)	800.00	sqm			
1.03	od21580/2018_2019 : Dismantling ridge tile from the roof and stacking carefully for reuse.	130.00	metre			
1.04	od146943/2018_2019 : Fixing on roof pressed clay tile (ridge and hip tile) of 20 mm nominal thickness and of approved size and as per approved pattern (old and new) set in cement mortar including finishing edges	130.00	metre			

1.05	od22013/2018_2019 : Supplying on roof pressed clay tile(Railway pattern tile) of 20 mm nominal thickness and of approved size and as per approved pattern	13750.00	E			
1.06	od22057/2018_2019 : Supplying on roof pressed clay tile ridge (Railway pattern) of 20 mm thickness and of approved pattern	1000.00	E			
1.07	9.1.1 : Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).Second class teak wood	1.22	cum			
1.08	od9195/2018_2019 : Readjusting and refixing the teak wood reapers in the roof by fixing with wire nails and replacing with departmental reaper in place of damaged and lost reapers.	350.00	sqm			
1.09	15.57 : Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-Charge	310.00	sqm			

1.10	12.52.3 : Providing and fixing tiled false ceiling of approved materials of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams per sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x 1.6 mm fixed to ceiling with 12.5mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85x	300.00	sqm			
1.11	14.69.1 : Varnishing with varnish of approved brand and manufacture:One or more coats with copal varnish	500.00	sqm			
1.12	14.52.1 : Painting with oil type wood preservative of approved brand and manufacture:Old work (one or more coats)	500.00	sqm			
1.13	14.53.1 : Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade:One or more coats on old work	1700.00	sqm			
1.14	14.43 : Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	500.00	sqm			

1.15	14.66.2 : Finish walls with Acryllic Smooth exterior paint of required shade:Old work (One or more coat applied @ 0.90 ltr/10 sqm)	500.00	sqm			
1.16	14.66.1 : Finish walls with Acryllic Smooth exterior paint of required shade:Old work (Two or more coats applied @ 1.67 ltr/10 sqm) on existing cement paint surface	800.00	sqm			
1.17	od148585/2018_2019 : Labour engaged for removing the furnitures, books, shelves and other manuscript materials carefully and rearranging after completion of the work	35.00	E			
1.18	od148596/2018_2019 : Hire charges for polytene Tarpaulin for covering the roof during dismantling the roof tiles for 800 sq.m.	10.00	Day			
Total in Figures						
Quoted Rate in Words						

CONTRACTOR

**sd/-
UNIVERSITY ENGINEER**