University of Kerala

Engineering Unit, Kariavattom

TENDER SCHEDULE FOR TILING OF FLOOR AND PROVIDING GRILL TO THE VERANDAH IN THE DEPARTMENT OF STATISTICS AT KARIAVATTOM

CAMPUS.							
Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount	
1	160	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm	m ²	1685.56	Rs.One thousand six hundred & eighty five & ps. Fifty Six only		
2	50	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. 9.48.1 Fixed to steel windows by welding	Kg	150.82	Rs.One hundred & Fifty & ps. Twenty six only	7541.00	
3	2	Labour engaged for doing carpentary works for doors and windows for laying tiles	DAY	749.93	Rs.Seven hundred & Forty Nine & ps. Ninety Three only	1499.86	
4	2	Labour engaged for lifting the furniture and books before tiling and rearranging after tiling	DAY	616.01	Rs.Six hundred & Sixteen & ps. One only	1232.02	
5	8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	m ²	112.99	Rs.One hundred & Twelve & ps. Ninety Nine only	903.92	
		TOTAL				280866.4	

PAC Rs.2,80,886/- (Rupees Two lakh Eighty two thousand Eight hundred & Eighty Six only)

1. I/We agreed to execute the work.	2% above the estimate rate.
2% below the estimate rate.	3. At the estimate rate.

sd/-

UNIVERSITY ENGINEER

CONTRACTOR