University of Kerala Engineering Unit, Kariavattom

Tender schedule for the Air-Condtioning work in the Scientometrics Lab at Department of Future Studies, Kariavattom (retender) Item rate)

SI.No.	Quar	ntity	Specification	Unit	Rate	Rate in words	Amount
1	2	nos		Е			
			Supply conveyance installation testing and commissioning of 2 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22/R32 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigent, electri cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue				
			Star/Daikan/Carrier/Panasonic/Mitsubishi) 100% copper				
2	2	nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement gaurantee and 3 year warranty				
3	2	nos	Supply and providing condensor stand	Е			
4	5	m	Extra length of copper pipe with wire and thermal insulation	m			
			TOTAL				

PAC Rs.

I/We agreed at quoted rates.

CONTRACTOR