

University of Kerala
Engineering Unit, Kariavattom

Tender Schedule for the work of laying vitrified tiles in the Department of Statistics at Kariavattom campus.

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	150	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	m ²	1787.95	Rs.One thousand Seven Hundred & Eighty Seven & ps. Ninety Five only	268192.5
2	3	Labour engaged for reducing the height of door for laying tiles carpenter 1 class.	E	815.22	Rs.Eight hundred & Fifteen & ps.Twenty two only	2445.66
3	3	Labour engaged for removing & replacing the furniture,coolie	E	616.01	Rs.Six hundred & Sixteen & ps.One only	1848.03
		Total				272486.2

PAC Rs.2,72,486/- (Rs.Two lakh Seventy Two thousand Four Hundred & Eighty Six only

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

CONTRACTOR

sd/-
UNIVERSITY ENGINEER

