

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM**

Tender schedule for the work of floor finishing in Post Office Area in Amenity building at Senate House campus.

| Sl.No. | Quantity | Specification | Unit | Rate | Rate in words | Amount |
|--------|----------|---|----------------|---------|---|-------------------|
| 1 | 140.00 | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm | m ² | 1613.27 | Rs. One thousand Six hundred & Thirteen & ps. Twenty Seven only | 225,857.80 |
| | | TOTAL | | | | 225,857.80 |

PAC Rs.2,25,857/- (Rs. Two Lakh Twenty five thousand Eight hundred & fifty Seven only)

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

CONTRACTOR

**sd/-
UNIVERSITY ENGINEER**