

**SCHEDULE****UNIVERSITY OF KERALA****SUBDIVISION II KARIAVATTOM****TENDER SCHEDULE FOR KARIAVATTOM CAMPUS -NEWLY CONSTRUCTED TOILET BLOCK AND WATER KIOSKS -SUPPLY AND INSTALLATION OF WATER PURIFIER CUM DISPENSERS FOR THE WATER KIOSKS**

<b>Sl. No</b>	<b>Item Description</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate / Unit</b>	<b>Rate in Words</b>	<b>Amount</b>
1)	od225655/2021_2022 Supply installation testing and commissioning of storage type water dispenser unit capable of storing 30/40 liters of normal and cold water each and 3/5 liters of hot water. The dispenser unit should be accompanied with matching type alpha UV water purifier. The dispenser should be made out of minimum 0.8mm thick sheet stainless steel and should have three faucets of brass chromium and three compartments of storing water. Polyurithane foam should be used for thermal insulation. The compressor to the cooling system should have refrigerant of R-134a / R-32-A. The guarantee period to the system is for a period of one year and servicing should be done four times in one year and attend complaints if any , promptly , which is exclusive of guarantee period service . (Make - Accura WHC , Bluestar , Acquaguard )	3	E	74128.79	Seventy Four Thousand One Hundred and Twenty Eight Rupees Seventy Nine Paise only	222386.37

**SCHEDULE**

	<b>TOTAL:</b>					<b>222386.37</b>
	<b>GRAND TOTAL after round off:</b>					<b>222386.00</b>

*(Rupees Two Lakh Twenty two thousand three hundred and Eighty six only)*

.....agree to undertake the above mentioned work:-

- 1) At the estimate rate.
- 2) At .....% below the estimate rate.
- 3) At .....% above the estimate rate.

Rate should be quoted both in figures and words

**CONTRACTOR**

**ASSISTANT EXECUTIVE ENGINEER II**