UNIVERSITY OF KERALA

ENGINEERING UNIT, KARIAVATTOM

Tender schedule for Providing additional grill shutters to the Ground Floor windows and enclosing GF roof opening of the court yard in the new block of CE building at SH campus.

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1		Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg	118.55	Rs. One hundred and eighteen and ps. Fifty five only	88,912.50
2		Supplying at site: Welded steel wire fabric of required width having rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer (Priming & painting to be paid for separately) 50x50mm Square mesh, 2.65 dia wires, 1.73kg/m2	kg	82.83	Rs. Eighty two and ps. Eighty three only	12,424.50
3		Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	sqm	154.90	Rs. One hundred and fifty four and ps. ninety only	11,617.50
	<u> </u>	TOTAL				112,954.50

1. I/We agreed to execute the work.	2% above the estimate rate.		
2 % helow the estimate rate	3 At the estimate rate		

CONTRACTOR UNIVERSITY ENGINEER