

University of Kerala
Engineering Unit, Kariavattom

Supply and installation of split type Air conditioners in connection with renovation of Computer Lab in the Department of Economics at Kariavattom Campus (Retender)							
Sl.No.	Qty		Specification	Unit	Rate	Rate in words	Amount
1	1	no	Supply conveyance installation testing and commissioning of 2 TR 5 star inverter type split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R410A CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerent, electric cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikin/Carrier/Mitsubhishi) 100% copper	E			
2	1	no	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)with 3 months replacement gaurantee and 3 year warranty	E			
3	1	no	Supply and providing condensor stand	E			
			TOTAL				
PAC Rs.							

I/We agreed to execute the work at quoted rates.

CONTRACTOR

Sd/-
UNIVERSITY ENGINEER