

UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM

TENDER SCHEDULE FOR THE URGENT REPAIR AND RECONSTRUCTION OF COLLAPSED BOUNDARY WALL BEHIND CENTRE FOR PERFORMING AND VISUAL ARTS BLOCK AND END PORTION OF HYMAVATHY POND AT KARIAVATTOM CAMPUS.

SI No	Qty	Specification	Unit	Rate	Rate in words	Amount
1	120	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	m2	9.93	Rs. Nine Ps. Ninety three only	1191.60
2	5	Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 (1 cement : 6 coarse sand etc complete	m3	5868.04	Rs.Five thousand eight hundred and sixty eight Ps. Four only	29340.20
3	12	Removing mortar from cement blocks and cleaning blocks and concrete articles(net quality of stacks of cleaned materials will be measured) in cement mortar	m3	392.14	Rs. Three hundred and ninety two Ps. Forteen only	4705.68
4	12	Solid block masonry using pre cast solid blocks (Departmental material) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 (1 cement : 6 coarse sand etc complete	m3	2697.11	Rs. Two thousand six hundred and ninety seven Ps. Eleven only	32365.32

5	12	Labour engaged for conveying cement blocks and construction materials by head load to the collapsed areas.	Nos	589.56	Rs. Five hundred and eighty nine Ps. Fifty six only	7074.72
TOTAL					Rs	74678

Rs. 74678/- (Rupees Seventy Four thousand six hundred and Seventy Eight only)

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

sd/-

CONTRACTOR

UNIVERSITY ENGINEER