UNIVERSITY OF KERALA

ENGINEERING UNIT, KARIAVATTOM

TENDER SCHEDULE FOR THE CIVIL WORK FOR SETTING UP OF KERALA UNIVERSITY BUSINESS INNOVATION AND INCUBATION CENTRE (KUBIIC) AT KARIAVATTOM CAMPUS

	Carrain (carrain) and carrain estimates						
Sl No	Qty	Specification	Unit	Rate	Rate in words	Amount	
1	6	Od Labour engaged for removing the mat on the floor of the room and cleaning the surface and bringing the mat to the store of the Engineering store as per departmental directions. Coolie	Nos	589.56	Rs. Five hundred and eighty nine Ps. Fifty six only	3537.36	
2	125	11.41 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 11.41.4 Size of Tile 1000x1000 mm	m2	2838.39	Rs. Two thousand eight hundred and thirty eight Ps. Thirty nine only	354798.75	
3	12	Od. Providing and fixing superior quality roller blinds with all fittings	m2	1248.61	Rs. One thousand two hundred and forty eight Ps. Sixty one only	14983.32	
4	30	14.58 French spirit polishing : 14.58.1 One or more coats on old work	m2	146.07	Rs. One hundred and forty six Ps. Seven only	4382.10	

5	225	14.53 Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: 14.53.1 One or more coats on old work	m2	76.21	Rs. Seventy six Ps. Twenty one only	17147.25
	TO					394849

PAC:- Rs.3,94,849 /- (Rupees Three lakhs ninety four thousand eight hundred and forty nine only)

I/We have undertake to execute the work at							
a)% below estimate rate.	b) At estimate rate						
c)% above estimate rate.							

sd/CONTRACTOR UNIVERSITY ENGINEER