

University of Kerala
Engineering Unit, Kariavattom

Tender Schedule for the work of laying vitrified tile flooring after dismantling the existing worn out terracota tile in the Department of Library and Information Science at Palayam.

Sl.No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1	151	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	m ²	41.36	Rs.Forty one & ps.Thirty Six only	6245.36
2	151	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600x600 mm	m ²	2062.11	Rs.Two thousand & Sixty Two & ps.Eleven only	311378.6
3	15	Labour engaged for removing & replacing the furniture,coolie	E	560.46	Rs.Five hundred & Sixty & ps.Forty Six only	8406.9
		Total				326030.9

PAC Rs.3,26,031/- (Rs.Three lakh twenty Six thousand & Thirty One only

I/We agreed to execute the work.

1.% above the estimate rate.

2.% below the estimate rate.

3. At the estimate rate.

CONTRACTOR

sd/-
UNIVERSITY ENGINEER