

UNIVERSITY OF KERALA

ENGINEERING UNIT KARIYAVATTOM

Tender Shedule for the Replacing collapsible shutter with grill door to increase the height of door opening in the GF varandah of Senate Hall Building at SH Campus

SL NO	Qty	Specificaations	Unit	Rate	Rate in Words	Amount
1	23.616	od253978/2020_2021 labour engaged for removing the collapsible shutter with fittings	Sqm	88.43	Rupees Eighty Eight,Ps: Fourty Three Only	2088.36
2	2.00	od253979/2020_2021 Labour engaged for cleaning the surface including disposal of the debris within a distance of 150m	Each	589.56	Rupees Five Hundred Eighty Nine Ps: Fifty Six Only	1179.12
3	1067.200	Item Shifted to head 14 as item 14.74Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	118.55	Rupees One Hundred Eighteen Ps: Fifty Five Only	126516.56

4	26.680	13.62.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	grill_\$H Sqm	154.90	Rupees One Hundred Fifty Four Ps: Ninty Only	4132.73
		TOTAL				133917.00

PAC :- Rs (133917/- Rupees One Lakh Thirty Three Thousand Nine Hundred Seventeen Only)

I/we agreed to execute the work

1.....% above the estimate rate

2% below the estimate rate

3 at the estimate rate

CONTRACTOR

sd/-
UNIVERSITY ENGINEER