

UNIVERSITY OF KERALA							
ENGINEERING UNIT, KARIAVATTOM							
TENDER SCHEDULE FOR AIRCONDITIONING WORK FOR MODIFICATION OF PLANT CULTURE LAB AT ROOM No.106 AT THE DEPARTMENT OF BIOCHEMISTRY AT KARIAVATTOM CAMPUS - RETENDER							
Sl No	Qty	Unit	Description of Item	Unit	Rate	Rate in words	Amount
1	2	Nos.	Supply, installation, testing and commissioning of 1 TR minimum 3 star split air conditioner unit with low power consumption, high wall mounting split type suitable for operating on 230V, 50Hz single phase AC supply and fitted with rotary compressor operating on R22/non CFC refrigerant with condensing and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerant, electric cable, copper pipe and thermal insulation upto 3 m. as required with one year warranty for machine and one year free services (VOLTAS/CARRIER/BLUE STAR)	Each			
2	2	Nos.	Supply and installation of 3 KVA Voltage Stabilizer suitable for Split type Air Conditioner with Voltage range of 175 to 275 and out range 210 to 240 V (V Guard)	Each			
TOTAL							

PAC :

Agreed at quoted rates.

UNIVERSITY ENGINEER

CONTRACTOR

