

University of Kerala
Engineering Unit, Kariavattom.

Tender Schedule for the work of Supply and installation of Split type Airconditioner in the Department of Economics-scheme on study on the cost of cultivation of Principal Crops in Kerala.

Sl.No.	Quantity		Specification	Unit	Rate	Rate in words	Amount
1	2	no	Supply conveyance installation testing and commissioning of 2 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerent, electric cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikan/Carrier) 100% copper	E			

2	6	nos	Supply conveyance installation testing and commissioning of 1.5 TR 5 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerent, electric cable, copper pipe and thermal insulation up to 4 M as required with two year on site warranty , 5 year compressor warranty and one year free service. (Voltas/ Blue Star/Daikin/Carrier) 100% copper	E			
3	2	nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)	E			
4	6	nos	Supply of 4 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)	E			
5	8	nos	Supply and providing condensor stand	E			
			Total Rs.				

PAC

I/We Agreed at Quoted rates.

UNIVERSITY ENGINEER

CONTRACTOR.