



UNIVERSITY OF KERALA  
DEPARTMENT OF ARCHAEOLOGY

Kariavattom Campus, Thiruvananthapuram – 695 581  
Kerala, India

Phone: 0471-2308054; Email: archeology@keralauniversity.ac.in

No. KU/ARC/69B/2025-26

Date: 14.07.2025

**QUOTATION NOTICE**

Quotations are invited for the purchase and installation of Air Conditioners for the Department of Archaeology, University of Kerala, as part of the project '**Ichthyoarchaeological Study of Fish Remains from Harappan Sites in India**' vide UO No. 2105/2025/UOK (File Ref No. Pl.A1/SPG/2024-25/25) dated 12.03.2025. Technical specifications and quantities required for the same are listed. Sealed Quotations are requested to be submitted to the address below **on or before 4.00 pm on 28.07.2025.**

- The undersigned reserves the right to reject any or all quotations without assigning any reason.
- The rate quoted should be inclusive of Tax, transportation charges and any other charges.
- Full payment will be made only after the satisfactory delivery of items.

Dr. Abhayan G.S.  
The Head  
Department of Archaeology  
University of Kerala  
Kariavattom campus  
Thiruvananthapuram  
Pin: 695581

### SCHEDULE OF ITEMS FOR AIRCONDITIONING ROOMS

Sr No	Description of Item	Unit of measure	Quantity	Rate
1	<p><b>BEE 5 STAR 2.0 TON HIGH WALL SPLIT AC</b>  Supply Installation Testing and Commissioning of 2.0 TON Hi Wall Split Air Conditioning Unit  Nominal Cooling Capacity (in BTU/Hr) -- 24000 BTU/Hr +- 10% Tolerance  Nominal marketing Capacity -2.0 TON  Latest BEE 5 STAR -Inverter variable Speed Compressor &amp; ISEER Ratings  Functions : Cooling,dehumidification, filtering and air circulation Inverter AC - Variable Speed Compressor  Copper Evaporator &amp; Condenser coils with Protective coating (Goldfin/Bluefin) Ecofriendly Refrigerant - R32/Equivalent Accessories - Remote with batteries, 3Meters Copper Coil with Class 0 Nitrile Rubber Insulation wound with all-weather tape, 4 Core wire - 3 Meters of suitable size, Drainpipes - Minimum 1.5 Meter.  Wall/Floor mounting metallic stands with Fasteners  Free periodical services as per OEM standards during Warranty period  Compressor Warranty minimum 5 years  PCB Warranty -5 years  Free Services - 2 per year  Brands - Mitsubishi/Daikin/Hitachi/Carrier/General/Bluestar</p>	Each	1	
2	<p><b>SITC of 5KVA Wall Mount Voltage stabiliser</b> for split AC unit with voltage range of 140-280 V stabiliser with Low and High Voltage Cut Off, Intelligent Time Delay, Thermal Overload Protection, Micro-controlled Circuitry, Digital Display, Fire retardant ABS Plastic Body, Wall Mountable Cabinet Design with 3 months replacement warranty and 3 years on site warranty. (V Gaurd VGA Series/Crompton PS Series/Microtek PEARL Series)</p>	Each	1	
3	<p><b>REFRIGERANT PIPING WITH ALL WEATHER TAPE</b>  Supply and installation of Refrigerant piping of suitable size matching the equipment size with 19mm thick nitrile rubber insulation with proper supports (Liquid &amp; Discharge Line) Copper Pipe - Totaline/Mandev make only, Nitrile Rubber Insulation - Armaflex/K flex, wound with All weather tape.</p>	Metre	2	

4	<b>POWER CABLE</b> Supply and drawing the following sizes of multi-core PVC insulated & FRLS PVC sheathed 650/1100 V grade copper conductor round flexible cables conforming to IS 694 part I 1960 in the existing surface / recess conduit as required including giving necessary connections of the following sizes. 4 core 2.50 sq mm	Metre	5	
5	<b>COMMUNICATION CABLE</b> Supply and drawing the following sizes of multi-core PVC insulated & FRLS PVC sheathed 650/1100 V grade copper conductor round flexible cables conforming to IS 694 part I 1960 in the existing surface / recess conduit as required including giving necessary connections of the following sizes. 4 core 1.50 sq mm	Metre	5	
6	<b>16A 3PIN PLUG TOP</b> Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS compliant )	Each	1	

*Sandhya N*  
05/06/2025

Assistant Engineer  
(Mechanical)  
University of Kerala

*R. M. N.*  
06/06/2025

Assistant Executive Engineer  
Electrical Section  
Engineering Unit  
University of Kerala  
Kariavattom Campus