

Schedule

UNIVERSITY OF KERALA						
SUB DIVISION I, KARIYAVATTOM						
Quotation schedule for the Urgent plumbing and toilet repair works at Womens Hostel Thycaud						
Date of Submission :- 10/07/2025			Time of duration :- 20 days			
Sl No	Quantity	Description of item	Unit	Rate	Rate in words	Amount
1	1.000	Dismantling water closet Indian/European type and disposal of the debris 150 m out side the area as per Dept direction	Each	490.60	Four hundred and ninety Rupees and sixty paise only	490.60
2	1.000	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid	Each	7102.28	Seven thousand one hundred and two Rupees and twenty eight paise only	7102.28
3	2.000	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Angle back wash basin size 600x480 mm with single 15 mm C.P. brass pillar tap	Each	2453.18	Two thousand four hundred and fifty three Rupees and eighteen paise only	4906.36

Schedule

4	10.000	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 25 mm pipe 12 kgf/cm ²	M	510.51	Five hundred and ten Rupees and fifty one paise only	5105.10
5	10.000	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work including cutting chases and making good the wall etc. 63 mm pipe 6 Kgf/cm ²	M	702.35	Seven hundred and two Rupees and thirty five paise only	7023.50
6	1.000	supplying and fixing Floor trap 110 mm with CP gratings	Each	606.32	Six hundred and six Rupees and thirty two paise only	606.32
7	2.000	Providing and fixing uplasticised PVC connection pipe with brass unions: 30 cm length 15 mm nominal bore	Each	95.89	Ninety five Rupees and eighty nine paise only	191.78
8	2.000	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931 15 mm nominal bore	Each	641.41	Six hundred and forty one Rupees and forty one paise only	1282.82
9	15.000	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	Each	908.11	Nine hundred and eight Rupees and eleven paise only	13621.65

Schedule

10	3.000	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete. 10 litre capacity - White	Each	1311.44	One thousand three hundred and eleven Rupees and forty four paise only	3934.32
11	1.000	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	Each	682.38	Six hundred and eighty two Rupees and thirty eight paise only	682.38
12	2.000	Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC. waste fittings complete. Semi rigid pipe 40 mm dia	Each	130.32	One hundred and thirty Rupees and thirty two paise only	260.64
13	1.000	Supplying and fixing CP Health faucet good quality including cost of materials and labour charges etc. complete as per the direction of site engineer-in-charge.	Each	758.61	Seven hundred and fifty eight Rupees and sixty one paise only	758.61
14	15.000	Providing and fixing wash basin 15 mm C.P. brass pillar taps,	Each	906.79	Nine hundred and six Rupees and seventy nine paise only	13601.85
15	10.000	supplying and fixing seat cover	Each	703.19	Seven hundred and three Rupees and nineteen paise only	7031.90
16	3.000	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet: 100 mm diameter	Each	213.24	Two hundred and thirteen Rupees and twenty four paise only	639.72

Schedule

17	8.000	Labour engaged for cleaning the sewer lines and manholes	Day	1106.22	One thousandone hundred and six Rupees and twenty two paise only	8849.76
Total Amount						76090
Rs 76,090 /- (Rupees :- Seventy six thousand and ninety only)						
I/We agreed to executive the work at 1).....% below estimate rate, 2) At estimate rate , 3).....% above estimate rate						
CONTRACTOR			ASSISTANT EXECUTIVE ENGINEER			

Name :-

Address :-