

UNIVERSITY OF KERALA

ENGINEERING UNIT SUBDIVISION I

Quotation scheduled for Urgent works for prevention of concrete spalling and other allied works at Thycaud Womens Hostel

Date of Submission 10/07/2025

TOC 15 days

SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	14.2	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	M2	57.76	Rs Fifty Seven Ps Seventy Six only	820.19
2	10	Removing and rooting out small / medium type banyan trees and other trees in walls and terrace area of the building, all labour charges, necessary chemical applying charges and rectification work with cement concrete and cement mortar etc; complete as per the direction of deptl; authorities. Removing banyan/ other trees	Each	435.38	Rs Four hundred Thirty Five Ps. Thirty Eight only	4353.80
3	5	13.16.1 6 mm cement plaster of mix:1:3 (1 cement : 3 fine sand)	M2	324.36	Rs Three Hundred Twenty Four ps. Thirty Six only	1621.80

4	3	26.29.1 Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars upto 12 mm diameter	Mtr	8.53	Rs Eight Ps. Fifty Three only	25.59
5	5	26.31.1 Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. SBR Polymer (@10% of cement weight) modified cementitious bond coat @2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer	M2	150.91	Rs One Hundred Fifty Ps. Ninty One only	754.55
6	5	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	M2	108.39	Rs One Hundred zero Eight Ps. Thirty Nine only	541.95

7	5	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shadeOld work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface	M2	139.17	Rs One Hundred Thirty Nine Ps. Seventeen only	695.85
8	1	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	M3	2177.17	Rs Two Thousand One Hundred Seventy Seven Ps. Seventeen only	2177.17
9	4.2	4.10 Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone III) : 4 graded stone aggregate 12.5 mm nominal size).	M2	475.38	Rs Four Hundred Seventy Five Ps. Thirty Eight only	1996.60
10	1	6.1.1 Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:4 (1 cement : 4 coarse sand) Terrace area main building	M3	8821.89	Rs Eight Thousand Eight Hundred twenty one Ps. Eighty Nine only	8821.89
11	4	OD42833/2025-2026 :Labour engaged for rooting out the existing banyan plants in the terrace area of the building	Each	1106.22	Rs One Thousand zero six Ps. Twenty Two only	4424.88

12	8.2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead:Cement mortar 1:4 (1 cement: 4 coarse sand)	M2	612.76	Rs Six Hundred twelve Ps. Seventy only	5024.63
13	3	OD49576/2025-2026 Labour engaged for cleaning the terrace area and dispose of the derbies with in a distance of 50 meters.	Each	1106.22	Rs one Ps.Ninty Four only	3318.66
	Total					34577.56
	After round off Total (Rs 34578 - Thirty Four Thousand Five Hundred Seventy Eight Only)					

1)Above the Estimate rate

2) Below the Estimate rate

3) At the Estimate rate

CONTRACTOR (Name and Address)

ASSISTANT EXECUTIVE ENGINEER

|