

UNIVERSITY OF KERALA							
ENGINEERING UNIT, KARIAVATTOM							
TENDER SCHEDULE FOR THE PROVIDING VINYL FLOORING IN THE ROOMS OF IT TRAINING CENTRE IN THE COMPUTER CENTRE BUILDING AT S.H. CAMPUS							
Sl No	Qty	Unit	Description of Item	unit	Rate	Rate in words	Amount
1	185	m ²	Providing 1.3mm thick Vinyl sheet of approved brand and colour over the existing cement flooring after levelling undulations if any in the floor by filling, pasting vinyl sheet with suitable adhesive firmly to the floor, rubbing hardly to remove air bubbles trapped while pasting etc. complete as per departmental direction.	m ²	683.73	Rupees Six hundred and eighty three and Paise seventy three only	1,26,490.05
2	5	Nos.	Labour for shifting furnitures and replacing after work. Coolie.	Each	540.53	Rupees Five hundred and forty and Paise fifty three only	2,702.65
TOTAL R							1,29,192.70

PAC Rs.1,29,193/- (Rupees One Lakh Twenty nine thousand One hundred and Ninety three only)

I/We agreed to execute the work.

1.% below the estimate rate.

2. % above the estimate rate.

3. At the estimate rate.

CONTRACTOR

UNIVERSITY ENGINEER

