

UNIVERSITY OF KERALA							
ENGINEERING UNIT, KARIAVATTOM							
TENDER SCHEDULE FOR AIRCONDITIONING WORKS FOR THE NEW BUILDING CONSTRUCTED TO HOUSE THE EQUIPMENTS OR FACILITIES UNDER PURSE PROGRAMME AT KARIAVATTOM CAMPUS							
SI No	Qty	Unit	Description of Item	Unit	Rate	Rate in words	Amount
1	17	Nos.	Supply conveyance installation testing and commissioning of 2 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 Hz single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc. including refrigerent, electric cable, copper pipe and thermal insulation up to 4 m. as required with one year warranty and one year free service (Voltas/Blue Star/Daikin/Carrier/LG) (100% Copper)	Each			
2	2	Nos.	Supply conveyance installation testing and commissioning of 1.5 TR 3 star split Airconditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 Hz single phase AC Supply and fitted with rotary compressor operating on R22 CFC refrigerent with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc. including refrigerent, electric cable, copper pipe and thermal insulation up to 4 m. as required with one year warranty and one year free service (Voltas/Blue Star/Daikin/Carrier/LG) (100% Copper)	Each			
3	17	Nos.	Supply and providing 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)	Each			
4	2	Nos.	Supply and providing 4 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard)	Each			

5	5	Nos.	Supply and providing timer suitable for 2TR AC unit	Each		
6	6	Nos.	Supply and providing condensor stand	Each		
TOTAL						

PAC :

Agreed at quoted rates.

UNIVERSITY ENGINEER

CONTRACTOR
