


| Estimate for telephone wiring at Aminity Centre | | | |
|---|---|--------|----------|
| S.No | PRODUCT DESCRIPTION | Unit | Quantity |
| Materials | | | |
| 1 | ARMOURED 12 Pair OFC Cable | Meters | 100 |
| 2 | 20 pair riser cable | Meters | 100 |
| 3 | 10 pair Riser cable | Meters | 300 |
| 4 | 2 pair phone Cable | Meters | 900 |
| 5 | krone Jumper Cable | Meters | 150 |
| 6 | RJ 11 connector | Nos | 50 |
| 7 | Roset Box | Nos | 40 |
| 8 | faceplate | Nos | 10 |
| 9 | RJ 11 socket | Nos | 50 |
| 10 | Pushbutton Phone | Nos | 20 |
| 11 | 100 pair Box | Nos | 3 |
| 12 | 50 pair box | Nos | 3 |
| 13 | 20 pair Box | Nos | 6 |
| 14 | ADC Krone 10 pair Module | Nos | 50 |
| 15 | Media Converter/LIU/Patch chord as needed | Nos | 2 |
| 16 | 8 Port Switch | Nos | 1 |
| 17 | 6U Rack , with power sockets, and accessories | Nos | 1 |
| 18 | HDPE Pipe | Meters | 75 |
| Labor Charge | | | |
| 19 | Laying of ARMOURED 12 Pair OFC Cable including Termination/splicing | Meters | 100 |
| 20 | Cabling through PVC conduit of suitable size | Meters | 1250 |
| 21 | Krone module termination | Nos | 50 |
| 22 | Phone Socket Termination | Nos | 20 |
| 23 | Installation and termination of 100/50/20pair box | Nos | 12 |
| 24 | HDPE laying | Meters | 75 |
| 25 | Trenching earth and Laying of HDPE, Baked brick layering, Refilling and restoration (For laying OFC). | Meters | 60 |
| 26 | Fixing and Dressing of wall mount rack | Nos | 1 |
| 27 | Fixing and Configuration of Switch/Media Converter/LIU etc.. | Nos | 2 |
| 28 | Wiring of electrical point for rack if needed | Nos | 1 |
| 29 | Additional items if any | Lt | 1 |
| 30 | Testing and Commisioning | Set | 1 |


Assistant Engineer (Ins.)
 Central Laboratory for Instrumentation
 and Facilitation
 University of Kerala
 Kanavattom Campus, 695 501