

## Tender Notice

Competitive quotations are invited from interested vendors inside Kerala for installation of CCTV at University College of Engineering ,Kariavattom ,in accordance with the specifications appended herewith and adheing to the following conditions:

1. The rate quoted should be inclusive of Tax, transportation charges, installation charges and any other charges.
2. Complaints with the items supplied should be rectified/replaced to the satisfaction of the University by the suppliers at their own cost.
3. Payment will be made only after the supply of the items at our site.
4. The undersigned reserves the right to reject/accept any quotation without assigning any reason.

The sealed quotations should be addressed to the undersigned super-scribing as 'Quotations for installation of CCTV at UCE,Kariavattom . The last date of receipt of quotations is at **3:00 p.m. on 04.08.2021**. The quotations will be opened at 3:30 p.m. on the same day in the presence of the vendors then present.

**15.07.2021**

**Sd/-  
Registrar**

<b>Sl No</b>	<b>Item</b>	<b>Qty</b>
1	32 Channel Professional NETWORK VIDEO RECORD SYSTEM	1 No
2	4 Mp IP bullet camera with microphone POE +20 MIR range ,Focal length between 2.8mm and 4 mm with mounting accessories	1 No
3	4 Mp bullet camera POE +20 MIR range ,Focal length between 2.8mm and 4 mm with mounting accessories	17 No
4	4 TB Hard Disk	2 No
5	16 port POE+ switch 10/100/1000	2 No
6	RJ45 Connector	50 No
7	RJ45 Boot Connector	50 No
8	Cat 6 UTP Cable	1600 M
9	4 U Network Rack with fan and 6 socket PDU	1 No
10	6 U Network Rack with fan and 6 socket PDU	1 No
11	25 mm ISI PVC white pipe with accessories	300 M
12	6A 3 Pin +Switch Electrical Point wiring	3 No
13	HDMI Extender over LAN -30M	1 No
14	43” LED Smart TV with wall mount accessories	1 No
15	1 KVA Online UPS with 1 hour battery backup	2 No
<b>Installation and Labour Charges</b>		
1	32 Channel Professional NETWORK VIDEO RECORD SYSTEM(including HDD) and configuring	1 No
2	4 Mp IP bullet camera with microphone	1 No
3	4 Mp IP bullet camera	17 No
4	16 port POE+ switch 10/100/1000	2 No
5	RJ45 Boot Connector termination	50 No
6	Cat 6 UTP Cable	1600 M
7	4 U Network Rack Fixing	1 No
8	6 U Network Rack Fixing	1 No
9	Laying 25 mm ISI PVC white pipe with accessories	300 M
10	Electrical wiring 6A 3 Pin +Switch	3 No
11	HDMI Extender over LAN -30M	1 No
12	Fixing 43” LED Smart TV with wall mount accessories	1 No
13	Unforeseen items	LS

