

DEPARTMENT OF LIBRARY & INFORMATION SCIENCE

UNIVERSITY OF KERALA

Thiruvananthapuram-695034

Re –accredited at the “A” Grade Level by NAAC



Dr. B. MINI DEVI

Head of the Department

dliskerala2@gmail.com

DLIS/ 645/ 2017

Phone: 0471-2308034

www.keralauniversity.ac.in/dlis

Date: 27/11/2017

Quotation Schedule

of Supply installation, testing and commissioning of 2T, 5 star split air conditioners with stabilizer and all accessories and allied Electrical Works in the Department

PART-I AIR CONDITIONERS						
Sl no	Qty		Specification	Unit	Rate	Amount (in Rs)
1	3	nos	Supply conveyance installation testing and commissioning of 2 TR 5 star split Air Conditioner unit with low power consumption high wall mounted suitable for operating on 230V, 50 HZ single phase AC Supply and fitted with rotary compressor operating on R22/R32 CFC refrigerant with copper condensing coil and evaporating units capable for cooling dehumidifying air circulating, microprocessor control with cordless remote etc including refrigerant, electric cable, copper pipe and thermal insulation upto 4Mtr as required with two year onsite warranty and five years compressor warranty. (Voltas /Blue Star/Daikin/o-General / Mitsubishi/Panasonic) 100 % copper	E		

2	3	nos	Supply of 5 KVA voltage stabilizer for split type AC unit with voltage range of 210-240V (V-Guard/ similar made) with 3 months replacement guarantee and 3 year warranty	E		
3	10	m	Extra length of copper pipe with wire and thermal insulation	m		
4	3	set	Supply and providing condensor stand	set		
			TOTAL			

PART –II- ELECTRICAL WORKS

Sl.No	Qty		Description in work	Unit	Rate	Amount in Rupees
1			Supply and fixing the following sizes of <i>PVC Conduit</i> conforming to IS 9537 / 1983 part III along with all required accessories <i>on surface</i> including making good the damages etc as required			
a	25	m	20 mm dia light guage	m		
2			Supply and drawing 650/ 1100 V grade <i>PVC insulated stranded single core copper conductor cables</i> conforming to IS 694 part I 1990 in the existing surface / recess conduit as required including giving necessary connections of the following sizes.			
a	30	m	2.50 sq mm 1 run	m		
b	30	m	4.00 sq mm 3 run	m		
3			Supply and Fixing the following types/ sizes of boxes suitable for modular accessories in surface /recess including making good the damages, colour washing etc as required (<i>Group B/ RoHS compliant</i>)			

a	3		2 module moulded plastic box on surface	E		
4			Supply and Fixing the following types/ sizes of front plates on the existing modular boxes (<i>Group B/ RoHS compliant</i>)			
a	3		2 module white/ off-white	E		
5			Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (<i>Group B/ RoHS compliant</i>)			
a	3	Nos	32 A DP switch with indicator	E		
b	3	Nos	25A socket			
			TOTAL			

ABSTRACT

			PART I- Supply and installation of Air conditioners			
			PART II – Electrical Works			
			Total			
			LS			
			Grand Total			

DEPARTMENT OF LIBRARY & INFORMATION SCIENCE

UNIVERSITY OF KERALA

Thiruvananthapuram-695034

Re –accredited at the “A” Grade Level by NAAC



Dr. B. MINI DEVI

Head of the Department

dliskerala2@gmail.com

DLIS/ 645/ 2017

Phone: 0471-2308034

www.keralauniversity.ac.in/dlis

Date: 27/11/2017

QUOTATION NOTICE

Quotations in sealed covers super scribing the name of work are invited from reputed suppliers/ licensed contractors for the following supply/work so as to reach the undersigned on or before 3.00 pm On 08-12-2017

Sl No	Name work	PAC
1	Supply installation, testing and commissioning of 2T, 5 star split air conditioners with stabilizer and all accessories	1,91,300/-
2	Petty electrical works in the department	10550/-

Quotation schedule and other details can be had from the office of the undersigned on all working days prior to seven days from the last date of receipt of quotations and up to 1.00 pm on the date of quotation. The schedule can also be downloaded from the University website. Rate should be quoted both in figures and words. Incomplete and late quotations will be summarily rejected. The rate quoted should be firm for 4 months. Selected. The undersigned reserves the right to reject any or all the quotations without assigning any reason whatsoever.

27-11-2017

Head of the Department

