

UNIVERSITY OF KERALA						
ENGINEERING UNIT SUBDIVISION I						
Quotation scheduled for Urgent maintenance works for prevention of rat infestation in Mess and Kitchen area at Thycaud Women's Hostel.						
Date of Submission 10/07/2025				TOC 10 days		
SL No	Quantity	Description	Unit	Rate	Rate in Words	Amount
1	32.738	<p>21.1.1.2</p> <p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc.</p> <p>Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately):</p> <p>For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)</p>	Kg	597.71	Rs Five Hundred Ninty seven Ps Seventy one only	19567.83

2	2	Providing and fixing 3mm thick ACP sheet, in paneling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer - in- Charge	M2	1002.60	Rs One Thousand zerozero two Ps Six zero only	2005.20
3	10.125	Providing and fixing aluminium powder coated shutter frame with steel powder coated mosquito net to windows / ventilations with necessary fittings including aluminium`hinges,tower bolt, Neoprene /EPDM rubber gasket etc complete as per the direction of Engineer in charge	M2	1410.13	Rs One Thousand Four Hundred ten Ps Thirteen only	14277.57
	Total					35850.60
	After round off Total (Rs 35851/- Thirty Five Thousand Eight Hundred Fifty one Only)					

1)Above the Estimate rate

2) Below the Estimate rate

3) At the Estimate rate

CONTRACTOR (Name and Address)

ASSISTANT EXECUTIVE ENGINEER

|