

UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM

Tender Schedule for raising the compound wall behind the University hostel for Women in Thycaud, Thiruvananthapuram.

No	Quantity	Description	Unit	Rate	Rate in words	Amount
1	9m ³	Dismantling clearing away and carefully stacking materials useful for reuse for any thickness of walls of brick laterite or rubble in cement mortar including disposal of debris within a distance of 150m.	M ³	694.00	Rs. Six hundred & ninety four only	6,246/-
2	20m ³	Cement solid block work in CM 1:6 of size 40x20x15cm including all charges for cost and conveyance, watering, curing etc complete	M ³	4550.00	Rs. Four thousand five hundred & fifty only	91,000/-
3	5250 dm ³	Reinforcement cement concrete 1:2:4 using 20mm broken stone for including all form work watering curing etc complete but excluding the cost of reinforcement for belt concrete.	10dm ³	85.00	Rs. Eighty five only	44,625/-
4	300kg	Providing reinforcement for RCC work, bent tied and placed in position using tor steel.	Qtl	7692.00	Rs. Seven thousand six hundred & ninety two only	23,076/-
5	300m ²	Plastering with cement mortar 1:4, 12mm thick one coat including watering curing etc complete.	10m ²	2069.00	Rs. Two thousand & sixty nine only	62,070/-
6	15m ³	Random rubble masonry in CM 1:6 for foundation and basement.	M ³	3582.00	Rs. Three thousand five hundred & eighty two only	53,730/-
7	50m ²	Pointing RR masonry with CM 1:3 including watering curing etc complete.	10m ²	945.00	Rs. Nine hundred & forty five only	4725/-
8	15Nos	Labour engaged for clearing the site etc complete Man mazdoor	E	434.00	Rs. Four hundred & thirty four only	6510/-
		Total				2,91,982/-

PAC Rs. 2,91,982/- (Rupees Two lakhs ninety one thousand nine hundred & eighty two only)

I/We agreed to execute the work. 1.% below the estimate rate.

2.% above the estimate rate. 3. At the estimate rate.

UNIVERSITY ENGINEER

CONTRACTOR