

**UNIVERSITY OF KERALA
ENGINEERING UNIT, KARIAVATTOM.**

**TENDER SCHEDULE FOR IMPLEMENTATION IT TRAINING CENTRE AND SOFTWARE DEVELOPMENT CENTRE
AT SH CAMPUS – CIVIL WORK**

Sl. No.	Quantity	Specification	Unit	Rate	Rate in words	Amount
1		Dismantling the existing flooring and aluminium partition (passage area)	LS			50,000.00
2	50m ³	Filling the deptl. earth conveyed from available place including consolidating well by layer to layer (ground floor) as per the direction of deptl. authorities	10m ³	335.00	Rs. Three hundred and thirty five only	1,675.00
3	6m ³	Plain cement concrete 1:4:8 using 40mm broken stone including ramming watering curing etc. Complete	M ³	5088.00	Rs. Five thousand and eighty eight only	30,528.00
4	85m ²	Plastering with CM 1:3, 12mm thick one coat floated hard and trowelled smooth etc.	10m ²	2124.00	Rs. Two thousand one hundred and twenty four only	18,054.00
5	1172m ²	Scraping and cleaning old painted surface with sand paper etc. Complete	10m ²	436.00	Rs. Four hundred and thirty six only	51120.00
6	1200m ²	Painting with ready mixed plastic emulsion paint two coat complete.	10m ²	838.00	Rs. Eight hundred and thirty eight only	1,00,560.00
7	100m ²	Flooring with vitrified floor tiles (stain free tiles) 60x60cm set in grout (Fevimate) over the existing plastered surface.	M ²	1217.00	Rs. One thousand two hundred and seventeen only	1,21,700.00
8	15m ²	Alu. Partition (as per the direction of deptl. authorities)		LS		41,000/-
		TOTAL				4,14,637/-

PAC Rs. 4,14,637/- (Four lakhs fourteen thousand six hundred and thirty seven only)

1. We agreed to execute the work. I percentage above the estimate rate
2. percentage below the estimate rate
3. At the estimate rate.

UNIVERSITY ENGINEER

CONTRACTOR